# National Register of Historic Places Inventory—Nomination Form


For NPS use only

received date entered

See instructions in *How to Complete National Register Forms*Type all entries—complete applicable sections

1,000	Nam	ecomplete ap	pilcable se	CHOITS					
histor			-Kansas Pı	ublic Lar	nd Survey	Thematic Group		# RH00- # JF00-	
2.	Loca			<del></del>			Olivinia de la compansión	<del>i andres en </del>	mannoonemeneemeneemeneem
street	& number	See Cont	inuation S	Sheet	OFFICE AND		N/A no	t for publi	cation
city, t	own	N/A		N/A vi	icinity of				
state		N/A	code	N/A	county	N/A		code	N/A
3.	Clas	sificati	on						
t 8 8	district building(s) structure site	Ownership  X public X private both  Public Acqui  A in proces being cor	sition s	Accessib yes: r	cupied in progress le	Present Useagriculturecommerciaeducationasovernmeaindustrialmilitary	al al eent nt	_ museum _ park _ private r _ religious _ scientific _ transpor _ other:	esidence
4.	Own	er of P	roperi	ty					
name		'See Cont	inuation S	Sheet					
street	& number	N/A							A CONTRACTOR OF THE CONTRACTOR
city, t	own	N/A		<u>N/A</u> vi	icinity of		state N/A		
5.	Loca	tion of	Lega	il Des	cripti	on			
court	house, regis	try of deeds, et	c. See Co	ontinuati	ion Sheet		-		
street	& number	N/A			**************************************				
city, t	own	N/A					state N/A		
6.	Repr	<u>esent</u> a	ition i	n Exi	sting	Surveys			
title	Nebraska	Historic 1	Buildings	Survey	has this pro	perty been determi	ned eligible?	) ye	s <u>X</u> n
date		On-going				federal	X state	county	loca
depos	sitory for sur	vey records	Vebraska (	State His	storical S		***************************************		
city, t	own	Lincoln					state Nebr	aska	

### National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Location

item number


Page

Each monument marks the actual point where several counties meet. Since the monuments are larger than a point, they lie in more than one county.

#### DEIOO 062

RH00-062						
Vicinity of Rulo Nebraska Kansas	code code	- <del>-</del>	counties counties	Richardson Brown Doniphan	code code	
JF00-072						
Vicinity of Mahas	ka					
Kansas	code	020	counties	Republic Washington	code	157 201
Nebraska	code	031	counties	Jefferson Thayer	code	095 169

## National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Owner of Property

Item number

Page

e 1

The actual survey monuments are part of the public domain, which is administered by the Bureau of Land Management. The land on which the monuments lie is owned by various public and private individuals.

Department of the Interior Bureau of Land Management Denver Federal Center-Building 50 6th Kippling Street Denver, Colorado 80225

#### RH00-062

HBJ Farms, Inc. White Cloud, Kansas 66094

Leonard H. Fee and Pauline Fee Rural Route Hiawatha, Kansas 66434


#### JF00-072

Leslie J. Cossaart Rural Route Mahaska, Kansas 66955

Walter M. and Frances Schnelle 618 Woodland Drive Washington, Kansas 66968

Nebraska Board of Educational Lands & Funds P.O. Box 94986 Lincoln, Nebraska 68509-4986

### National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Local of Legal Description Rem number

Page

e 1

RH00-062 Register of Deeds Richardson County Courthouse Falls City, Nebraska 68355

Register of Deeds Brown County Courthouse Hiawatha, Kansas 66434

Register of Deeds Doniphan County Courthouse Troy, Kansas 66087

JF00-072 Register of Deeds Jefferson County Courthouse Fairbury, Nebraska 68352

Register of Deeds Thayer County Courthouse Hebron, Nebraska 68370

Register of Deeds Republic County Courthouse Belleville, Kansas 66935

Register of Deeds Washington County Courthouse Washington, Kansas 66968

### 7. Description

Condition X excellent	X_ deteriorated	Check one _X_ unaltered	Check oneX original sit	e
good fair	ruins _X_ unexposed	altered	•	dateN/

Describe the present and original (if known) physical appearance

The cast iron monument marking the point of intersection of the  $40^{\circ}$  North latitude line and the bluff on the west bank of the Missouri River is six feet high and tapers from a 16" base to 7" at its top. Its north side is marked "Nebraska", the south "Kansas", the east "1854", and the west " $40^{\circ}$  N. Lat.". It is located by four witness stones 12" x 3", set 10 feet from the monument. The sandstone monument marking the point of intersection of the Sixth Principal Meridian and the 40°N latitude base line is 14" high with small stones anchoring the base. the extant portion of the original 48"x15"x6" monument. extant are two of the four witness stones set 10 feet from the monument. The stone to the south is sandstone and measures 21"x11"x2" and the one to the west is limestone, measuring 18"x10"x3". This is a thematic nomination that consists of two separate sites with a total of eight contributing objects (five and three each).

RH00:062 This monument is a hollow cast iron shaft 1" thick, weighing between 500 and 600 pounds. It is six feet high with a flange base 16"x16". Directly above the base it is 11"x11" tapering to 7"x7" at the top which is beveled. The monument is marked on its four sides with raised cast upper case Roman letters that are 1 1/4" high. The north side reads "Nebraska", the south "Kansas", the west "40°N. Lat.", and the east "1854". A St. Louis company cast the monument in 1854. It was set in place on May 8, 1855, by Charles A. Manners, a U.S. Deputy Surveyor. Manner's field notes state that "said monument or cast iron post was erected by setting the same two feet in the ground with a flat stone well bedded underneath it for a foundation and the excavation around the post well rammed with earth and small stones...the sides of the monument facing the cardinal points". Manners also set four stones about 12 inches in width and 3 inches thick in the ground ("witness stones") about one foot deep and ten feet from the monument, one in each of the cardinal directions, which he connected by a trench ten inches deep. marked four black oak trees, one in each of the four sections that meet at the monument, indicating the appropriate section, township and range for each.

In 1924, after having been toppled and set upright in an erroneous location, the monument was reset in a sturdier foundation. Leo M. Petersen set a cement base 14x30x30 inches on top of the original limestone base. At the exact point of intersection of the lines connecting the witness stones he set (14 inches deep in the cement base and resting upon the limestone) an iron

# National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Description

Item number

Page 2

pipe three feet long and three inches in diameter, with a brass cap on the top marked "Kansas Initial Corner 1924" and "SC TIN", "R18E S36" and "R19E S31." He then placed the original cast iron shaft down over the iron survey pipe and secured it with two strap irons on four bolts set firmly in the cement base. This monument stands today in an excellent state of preservation. It is six and one-half miles southeast of Rulo, Nebraska, about 200 feet west of the road between Rulo and White Cloud, Kansas, and on top of the first bluff bank overlooking the Missouri River to the east. It stands on the point where the parallel of 40°N latitude (Kansas-Nebraska state line) intersects the top of the bluff on the west bank of the Missouri River, and marks the initial point of survey for Kansas and Nebraska.

JFOO:072 This monument was set June 11, 1856, by Charles A. Manners in a flat area of prairie at the point where the Sixth Principal Meridian intersects the  $40^{\circ}$  N latitude base line (the point where present day Thayer and Jefferson Counties, Nebraska, and Washington and Republic Counties, Kansas, meet). Made from red sandstone, the mounument measured  $48"\times15"\times6"$  and was set to correspond with the cardinal points, with its flat sides facing north and south and its edges east and west. The north face was inscribed with the letter "N" and "T1N", while the south face read "K" and "T1S". The east side was inscribed with "R1E" and the west with "1856" and "R1W". Manners field notes state that the stone was set "2 ft in the ground and firmly fastened with smaller stones about its base". Following accepted procedure, Manners also set witness stones at a distance of ten feet from the monument in each of the cardinal directions. He describes them as follows:

"on the North Limestone 20x10x2 on the East Limestone 19x11x3 on the South Limestone 21x11x2 on the West Limestone 18x10x3"

Present day surveyors had taken the location of this monument for granted, although it was not visible above ground. It was unearthed in 1976 by the U.S. Geodetic Survey and then reburied, since it lies in the center of a county road. On October 25, 1986, 16 surveyors representing five states once again unearthed the monument. Buried in the ground was the bottom 14" of the sandstone marker with small stones about its base. Also found was the sandstone set ten feet to the south and the limestone set ten feet to the west. The upper approximately 34" of

# National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Description

Item number

7

Page 3

the monument had apparently been broken off at a much earlier time. The top 8" had been found in a nearby ditch by the owner of adjacent property. Visible on that portion was "1856" and "R1W". The group of surveyors spearheading the project to locate the monument intend to excavate the adjacent area in the spring of 1987 hoping to locate the two remaining witness stones and the middle portion of the monument, with the goal of restoring it.

### 8. Significance

1400-1499 1500-1599 1600-1699 1700-1799 1800-1899	Areas of Significance—C archeology-prehistoric agriculture architecture art commerce communications	community planning conservation economics education engineering X exploration/settlement	***************************************	literature military music	 religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	1855, 1856 to 1937	Builder/Architect N	/A		 N

#### Statement of Significance (in one paragraph)

These surveyors' monuments and the witness stones that locate them are significant on the state level in the area of settlement for their role in the surveying of the public domain and resultant land transfer in five states. The cast iron monument located on a bluff above the Missouri River marks the initial point for survey in Nebraska and Kansas and was the reference point for survey in much of the first settled areas of these two states. The sandstone monument marks the intersection of the Sixth Principal Meridian and its base line (40° N latitude parallel) from which public lands were surveyed in all of Kansas and Nebraska and parts of Wyoming, Colorado and South Dakota. Since these monuments have been used, from the time they were set up to the present for public land surveys, their significance ranges from 1855-56 to the present. Historically, however, this period would end in 1937.

#### HISTORY

The passage of the Kansas-Nebraska Act in 1854 opened vast amounts of the Public Domain for settlement. In Kansas, hundreds of Missourians, most of whom were pro-slavery, immediately staked claims just across the Kansas-Missouri border. While settlement proceeded somewhat slower in Nebraska, there was still an urgent need to locate and identify the land so that ownership could be easily transfered from the federal government to private individuals. Arrangements were quickly made for the region to be surveyed, starting at the Missouri River. On August 1, 1854, John Calhoun was appointed Surveyor General of Nebraska and Kansas. On August 26, 1854, the Commissioner of the General Land Office sent instructions to Calhoun to determine the location of the 40 N latitude parallel and to survey it west from the Missouri River. Captain Thomas J. Lee of the U.S. Topographical Engineers determined by astronomical observation the point of interstection of the 40°N parallell and the river. This point was to be the initial point for all survey in Nebraska and Kansas, and the  $40^{\circ}\,\mathrm{N}$  parrallel became the base line for surveys from the Sixth Principal Meridian (Sixth P.M.) as well as the boundary between Nebraska and Kansas. J.P. Johnson, a deputy surveyor set an oak post at the initial point on November 17, 1854, and proceeded to survey west 108 miles to the Sixth P.M.

## National Register of Historic Places Inventory—Nomination Form

Fer NPS use only received date entered

Continuation sheet

Significance

Item number

8

Page

The cast iron monument marking the initial point was ordered by Captain Lee when he returned to St. Louis, with the instructions that upon completion it be forwarded up river "with the least delay" so that Johnson could set it. Late in the year 1854 Lee returned to St. Joseph to discover that the monument had only just arrived there. He stored it with Messrs. Donnell, Saxton and Potee, advised the Surveyor General of the situation and suggested that the monument be planted the next year. In April, 1855, U.S. Deputy Surveyor Charles A. Manners was issued instructions to set the iron monument, which he did on May 8, 1855. Manners also set four witness stones and marked four black oak trees.

At this same time, Manners was instructed to examine Johnson's survey of the 40°N base line, which he found grossly in error. He resurveyed the entire 108 miles of the base line and marked its point of intersection with the Sixth P.M. on June 11, 1856. He set the sandstone monument and four witness stones which he connected with a 7" elevation of earth.

In 1924 Leo M. Petersen, a U.S. Surveyor from the Government Land Office was instructed to restore the initial corner of the Kansas and Nebraska Public Surveys. He discovered that the cast iron monument had been toppled from its original base and set upright 2 1/2 feet to the north. The excavation of the witness stones and faint surface indications of a rectagular trench verified this relocation. On June 28, 1924 Petersen set a cement base on top of the original limestone base. In the cement he set an iron pipe with a brass cap marking the location. He then placed the original cast iron shaft over the pipe and secured it. His work has held the monument in place to the present day.

The sandstone monument marking the Sixth P.M. was apparently broken off and covered by roadbed many years ago. It has been unearthed and covered over at least three times: in 1976 by the U.S. Geodetic Survey, in 1985 by Larry Goracke, appointed Jefferson County Surveyor, and in 1986 by a group of surveyors from five states sponsored by the Professional Surveyors Association of Nebraska. The surveyors unearthed the base and lower portion of the shaft and have located the top portion of the monument. Their goal is to locate the missing middle section and completely restore the monument.

# National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Significance

Item number

8

Page 3

#### SIGNIFICANCE

These surveyors' monuments and the witness stones which locate them are significant on the state level in the area of settlement for their role in the surveying of the public domain and resultant land transfer in five states. The period of significance begins with the setting of each monument. They were used by surveyors from that date on and are used today for the same purposes. Historically, the period of significance, by definition, would end in 1937.

Public lands date from the formation of the United States. The federal government acquired land through cession, treaty and purchase. Nearly two billion acres of land in 32 states (4/5 of the gross area of the U.S.) at one time or another have been part of the Public Domain. This land was transferred to private individuals by various types of land grants and through sale authorized by Public Land Laws.

Shortly after the formation of the United States, the federal government conceived an idea for a method to accumulate funds for its depleted treasury and to protect its western borders. It would sell land from its vast western (west of the Appalachians) holdings. To do so, the land had to be accurately located and described. In 1784, the Continental Congress appointed a committee to develop a plan to facilitate such transactions. The result was the 1785 Land Ordinance whose provisions determined the shape of land parcels, the numbering system for land division and the terms for purchase. A 1796 revision of this ordinance substanially reflects the system in use today.

The method for land location is called the rectangular survey system (sometimes referred to as the "township and range" system). Survey begins at the "initial point", which is the intersection of a principal meridian (a true meridian) and a base line, (run at right angles to the p.m.) of which there are 31 in the contiguous U.S. and five in Alaska. (see map) Six-mile-square townships are laid out and numbered north and south of the base line. A line or column of townships is called a range and they are numbered east or west of the principal meridian. Each township is divided into one-mile-square sections (640 acres) numbered from 1 to 36. The sections can be further subdivided and thus described and identified. Field and fence lines and road networks follow this rectangular system of land division, resulting in the now familiar pattern of squares, rectangles and right angles of the rural landscape.

## National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Significance

Item number

8

Page

In surveying public lands, monuments are set with the intention of establishing a permanent marking of the lines and fixing the corner positions so that the location of the surveyed lands may always be definitely known. Witness stones are set to verify exact location of the monuments. Once monuments have been set and the survey accepted, they cannot be changed, even if technical error is later identified. These surveys are called cadastral surveys and are "the foundation upon which rests title to all land that is now, or was once, part of the Public Domain of the United States" (Cazier, p.107).

In Nebraska and Kansas survey was begun in 1854 with the determiniation of the  $40^\circ$  N latitude line (which became the base line for the Sixth P.M.) and its intersection with the Missouri River. This point, marked by the cast iron monumnent in Richardson, Doniphan and Brown counties, is the initial point for survey in Nebraska and Kansas, and was the reference point for land survey in much of the first settled areas of these two states. The  $40^\circ$  N line was run only 108 miles west to the Sixth Principal Meridian because of apprehensions of Indian interruption and because it was thought that settlement would not occur any further west. In fact the survey instructions do not include the Sixth P.M. They state:

At some future time, when necessary, it is proposed to start a principal meridian, extending on the north of such base to the Missouri river in Nebraska, and on the south of the same to the southern boundary of Kansas, which is the 37th parallel of north latitude. Although the public surveys will count from the principal meridian precisely as if the same were surveyed, the labor of such meridian survey will be now omitted, and that labor will be directed to insure practical results of more immediate importance. (Committee, p. 4)

In 1858-59, however, the line was extended west to the Rocky Mountains. This base line and the corresponding Sixth Principal Meridian, marked by the sandstone monument in Thayer, Jefferson, Washington, and Republic counties, serve as the reference points for survey of public lands in all of Kansas and Nebraska, and approximately 95% of Wyoming, 75% of Colorado and 15% of South Dakota. (see map) These two monuments not only represent the larger survey system that made possible the rapid settlement of the western United States, but are also actual monuments, marking major points of reference, that have been used every day since they were set by public land surveyors in a five state area.

# 9. Major Biblio( aphical Reference:

See Continuation Sheet

10. Geographical Data	See Continuation Sheet
Acreage of nominated property N/A	
Quadrangle nameN/A	Quadrangle scale <u>N/A</u>
UTM References	
	D
Zone Easting Northing	Zone Easting Northing
c	· D
	F
	tandaria tandaria de la constanta de la consta
	HLLJ LJLLJ LLLJLJ
Verbal boundary description and justification	
N/A	
• •	
List all states and counties for properties over	rlapping state or county boundaries
state N/A code	code
state N/A code	county code
11. Form Prepared By	
II. FORIII FIENAICU DY	
name/title See Continuation Sheet	
Bee Continuation Sheet	
organization N/A	date N/A
street & number N/A	telephone N/A
city or town N/A	state N/A
12. State Historic Pres	ervation Officer Certification
The evaluated significance of this property within the	state is:
national X_ state	local
	for the National Historic Preservation Act of 1966 (Public Law 89–
665), I hereby nominate this property for inclusion in according to the criteria and procedures set forth by	the National Register and certify that it has been evaluated
	KI have as
State Historic Preservation Officer signature	mer a Junion
title Director, Nebraska State Historic	al Society date $4/30/87$
For NPS use only	
I hereby certify that this property is included in	the National Register
	date
Keeper of the National Register	
Attest:	。由于自己的基础是在企业的企业是自己的企业的企业。 (1)(1)(1)(1)(1)(1)(1)(1)(1)(1)(1)(1)(1)(
Chief of Registration	그는 하는 사람들은 얼마 하는 하는 사람들이 가장 하는 사람들이 가장 하는 사람들이 되었다. 그는 사람들이 함께 함께 함께 되었다.

## National Register of Historic Places Inventory—Nomination Form

For NPS use only received date entered

Continuation sheet

Bibliography

Item number 9

Page 2

Andreas, A. T. History of the State of Kansas. Chicago: A. T. Andreas, 1883.

Brinker, Russell C. and Paul R. Wolf. **Elementary Surveying**, Seventh Edition. New York: Harper and Row, Publishers, Inc., 1984.

Cazier, Lola. Surveys and Surveyors of the Public Domain 1785-1975. Washington, D.C.: U.S. Government Printing Office, n.d.

Committee on Social Science Studies, University of Kansas Publications. Territorial Kansas. Lawrence: The University of Kansas Press, 1954.

Lee, Captain Thomas J. Report upon the determination of the intersection of the Parallel of 40 N. Lat. with the Missouri River. Washington, December 23rd, 1854.

Manners, Charles A. Field notes, May 8, 1855; June 11, 1855; June 14, 1855.

Petersen, Leo M. Report of restoration Initial Corner of Kansas and Nebraska Public Land Surveys, "Special Work", Nebraska, in The Nebraska Surveyor, 5:2 (April-June, 1986): 8-12.

"Search Is On for Key Surveyors' Monument." Omaha World-Herald, October 25, 1986, p. 13.

Sheldon, Addison Erwin. **History and Stories of Nebraska**. Chicago: The University Publishing Co., 1914.

"Surveyors locate historic 1856 marker." Lincoln Sunday Journal-Star, October 26, 1986.

"'This must be the place' was right and significant marker was found." Lincoln Sunday Journal-Star, March 24, 1985, p. 28.

U.S. Department of the Interior, Bureau of Land Management. Manual of Instructions for the Survey of the Public Lands of the United States, Technical Bulletin 6. Washington, D.C.: U.S. Government Printing Office, 1973.

## National Register of Historic Places Inventory—Nomination Form

Positive usersity
received
date entered

Continuation sheet

Geographic Data

Item number 1

Page

RH00-062

Acreage of nominated property <u>less than one</u> Quadrangle name <u>Big Lake</u>, <u>MO-Nebr</u>. UTM Reference

Quadrangle scale 1:24,000

Zone 15, Easting 300925, Northing 4430000

Verbal boundary description and justification


The area to be nominated is a square measuring 14.14 feet per side, totaling 200 square feet. This area will include the monument and the four witness stones. It is determined by the location of the witness stones, which are 10 feet from the monument in each of the cardinal directions. The square is created by connecting the four stones. This follows the trench line that was dug in 1855. The result is a triangular parcel of land in each section that measures 10'x10'x14.14' and totals 50 square feet (see figure below). The triangular parcel is in the extreme corner of each of the following:

SE $\frac{1}{4}$  of SE $\frac{1}{4}$  of SE $\frac{1}{4}$  of Sec. 36 R18E T1N SE $\frac{1}{4}$  of SW $\frac{1}{4}$  of SW $\frac{1}{4}$  of Sec. 31 R19E T1N NE $\frac{1}{4}$  of NE $\frac{1}{4}$  of Sec. 1 R18E T1S NW $\frac{1}{4}$  of NW $\frac{1}{4}$  of NW $\frac{1}{4}$  of Sec. 6 R19E T1S


List all states and counties for properties overlapping state or county boundaries.

#### RH00-062

Nebraska code 031 counties Richardson code 147 Kansas code 020 counties Brown code 013 Doniphan 043



## National Register of Historic Places Inventory—Nomination Form



Continuation sheet Geographic Data

Item number

10

Page

Quadrangle scale 1:24,000

JF00-072

Acreage of nominated property less than one Quadrangle name Reynolds, Nebr.-Kans. UTM Reference

Zone 14, Easting 639228, Northing 4429040


Verbal boundary description and justification

The area to be nominated is a square measuring 14.14 feet per side, totaling 200 square feet. This area will include the monument and the two extant witness stones. It is determined by the location of the four original witness stones, which were set 10 feet from the monument in each of the cardinal directions. The square is created by connecting the location of the four stones. This follows the trench line that was dug in 1856. The result is a triangular parcel of land in each section that measures 10'x10'x14.14' and totals 50 square feet (see figure below). The triangular parcel is in the extreme corner of each of the following:

- SE4 of SE4 of SE4 Sec. 36 RIW TIN SW4 of SW4 of SW4 Sec. 31 R1E T1N NEW of NEW of NEW Sec. 1 RIW TIS NW4 of NW4 of NW4 Sec. 6 RIE T1S

List all states and counties for properties overlapping state or county boundaries.

JF00-072					
Kansas	code 020	counties	Republic	cođe	157
			Washington		201
Nebraska	code 031	counties	Jefferson	cođe	095
•			Thaver		169




NOMINATION BOUNDARY

TOWNSHIP LINE

WITNESS STONE

NON-EXTANT WITNESS STONE MONUMENT 1" = 13.3'

### National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Form Prepared By

Item number

11

Page <sup>1</sup>

Kathleen Fimple, Preservation Historian Nebraska State Historical Society P.O. Box 82554 Lincoln, Nebraska

December, 1986 (402) 471-4769

William L. Rynearson and Jack C. Fitch, Past Presidents
Professional Surveyor's Association of Nebraska
P.O. Box B (402) 563-5762
Columbus, Nebraska

Dec 600 is to concern

**Marginers** 

data amered

#### United States Department of the Interior National Park Service

## National Register of Historic Places Inventory—Nomination Form


State Historic Preservation Officer Certification


Continuation sneet	Item number		Page -
The evaluated significance of this pr	operty within the	state is:	
national	X state	loca	1
As the designated State Historic Pres	ervation Officer f	or the Nat	ional Historic
Preservation Act of 1966 (Public Law	89-665), I hereby	nominate t	his property for
inclusion in the National Register an	d certify that it	has been e	valuated according
to the criteria and procedures set fo	rth by the Nationa	ıl Park Ser	vice.
State Historic Preservation Officer s	ignature Scelle	arel D6	Panking
title Deputy State Hestone Reger		Date	5/18/87
1 0			


weed succession of the conditions

1881 8 8 MAL

Jell I Let







Area surveyed from 6TH P.M. (Excepting Wind River and Ute Meridians)

PHOTO #1 OF 4

NEBRASKA - KANSAS PUBLIC LAND SURVEY THEMATIC RURAL JEFFERSON + THAYER COUNTIES, NEBRASKA, REPUBLIC + WASHINGTON COUNTIES, KANSAS

Nembs # JFOO-072

BUREAU OF LAND MANAGEMENTDENVER SERVICE CENTER
OCTOBER, 1986 (D433)

VIEW LOOKING DOWN ON
MONUMENT IN EXCAVATED

SITE.

PHOTO # 2 OF 4

NEBRASKA - KANSAS PUBLIC, LAND SURVEY THEMATIC RUBAL RICHARDSON COUNTY, NEBRASKA, BROWN AND DONIPHAN COUNTIES, KANSAS

NeHBS # RHOO-062

RICHARD E. JENSEN
NEBRASKA STATE HISTORICAL SOCIETY
MAY, 1984 (8405/3:13)
VIEW LOOKING NORTHEAST

PHOTO #3 OF 4

NEBRASKA - KANSAS PUBLIC LAND SURVEY THEMATIC RURAL RICHARDSON COUNTY, NEBRASKA, BROWN AND DONIPHAN COUNTIES, KANSAS

NeHBS # RHOO-062

RICHARD E. JENSEN
NEBRASKA STATE HISTORICAL SOCIETY
MAY, 1984 (8405/3:11)
VIEW LOOKING SOUTHWEST

PHOTO # 4 OF 4

NEBRASKA - KANSAS PUBLIC LAND SURVEY THEMATIC RURAL RICHARDSON COUNTY, NEBRASKA, BROWN AND DONIPHAN COUNTIES, KANSAS

NeHBS #RHOD-062

RICHARD E. JENSEN
NEBRASKA STATE HISTORICAL SOCIETY
MAY, 1984 (8405/3:18)
VIEW LOOKING WEST